



GUIDEBOOK FOR BEST ENVIRONMENTAL PRACTICES

# NOISE CONTROL AT LTA SITES



All rights reserved. This publication is not for commercial purposes. It is intended for the use of the Land Transport Authority's officers and its contractors. No part of this publication may be reproduced or transmitted in any forms or by any means, in parts or whole, without the prior written permission of the Land Transport Authority.

Copyright © July 2013  
Land Transport Authority, Singapore

Published by Land Transport Authority

Enquiries can be directed to LTA Safety Division

# Acknowledgements

The Land Transport Authority (LTA) would like to thank the National Environment Agency (NEA) for their invaluable contribution and support in producing this guidebook.

Special thanks also go out to all staff who have provided constructive feedback and suggestions.

Lastly, a big thank you to all our contractors for their continuous support and efforts in maintaining an environmentally friendly site.

## ENVIRONMENTAL POLICY STATEMENT

LTA is committed to nurture its staff to care and protect our environment. We incorporate environmental protection in our strategic decisions and conduct our business in a manner that balances the environmental and economic needs of the communities in which we operate.

We will:

- o Comply fully with all relevant environmental legislation and regulations and meet or exceed good environmental practices;
- o Work with our partners i.e., transport operators, contractors, suppliers, interest groups and other government agencies in a concerted effort to operate in an environmentally responsible manner;
- o Create a cleaner and greener environment by making continuous efforts to be energy-efficient and to practice Reduce, Reuse and Recycle; and
- o Monitor, evaluate and continually improve our environmental management practices to ensure efficient use of the limited resources.



**Chew Hock Yong**  
Chief Executive

**Date: 1 September 2010**

# Contents

|  | Page       |
|--|------------|
| Chapter 1      Basic acoustics   | 1          |
| Chapter 2      Introduction to Noise Management on site                            | 6          |
| <b>Step 1:<br/>Meeting Regulatory and Other Requirements</b>                       | <b>10</b>  |
| Chapter 3      Regulatory and Other Requirements                                   | 11         |
| <b>Step 2:<br/>Identification of Noise Sensitive Receivers &amp; Noise Sources</b> | <b>30</b>  |
| Chapter 4      Noise Sensitive Receivers   | 31         |
| Chapter 5      Noise Sources on Construction Sites                                 | 36         |
| <b>Step 3:<br/>Management and Mitigation</b>                                       | <b>52</b>  |
| Chapter 6      Noise Management Plan   | 53         |
| Chapter 7      Basic Principles of Using Noise Barriers                            | 100        |
| <b>Step 4:<br/>Noise Monitoring</b>  | <b>106</b> |
| Chapter 8      Noise Monitoring  | 107        |
| <b>Step 5:<br/>Community Engagement</b>  | <b>114</b> |
| Chapter 9      Public Relations Work   | 115        |
| Appendix 1      Flowchart for the Process on Noise Management                      | 122        |
| Appendix 2      Format of report for Noise Management Plan                         | 124        |
| Appendix 3      Useful Information   | 125        |

# List of Acronyms

|            |  |
|------------|--|
| dB         | Decibel                                |
| dB(A), dBA | A-weighted decibels                    |
| DCM        | Deep Cement Mixing                     |
| ECO        | Environmental Control Officer          |
| EIA        | Environmental Impact Assessment        |
| kHz        | Kilohertz                              |
| Leq        | Equivalent Continuous Sound Level      |
| $L_{p(A)}$ | Sound Power Level at receiver's end    |
| LTA        | Land Transport Authority               |
| $L_{w(A)}$ | Sound Power Level at source            |
| m          | Metre                                  |
| NEA        | National Environment Agency            |
| NMP        | Noise Management Plan                  |
| NSR        | Noise Sensitive Receivers              |
| PH         | Public Holidays                        |
| PR         | Public Relation                        |
| PRO        | Public Relation Officer                |
| R          | Distance from source to receiver's end |
| SMS        | Short Message Service                  |
| SPL        | Sound Power Level                      |

# Chapter 1

## Basic Acoustics


### 1.1 Definition of Noise pollution

“Noise pollution is sound at excessive levels that may be detrimental to human health”

- Organisation for Economic Co-operation and Development, 2008


## 1.2 Wavelength

Wavelength is determined by the distance between any point on the wave and the equivalent point of the next phase.



## 1.3 Amplitude

Amplitude of a wave is its strength or power of a noise signal and is often the “height” of a wave when viewed on a graph. The higher the amplitude, the higher the volume would be.






# Chapter 1

## Introduction

### 1.4 Frequency


Frequency of a wave is the number of times the wavelength occurs in one second. It is measured in kilohertz (kHz) or cycles per second. Higher frequencies are interpreted as higher pitch.



### 1.5 Decibels

A unit (dB) used to measure the power of a signal, such as an electrical signal or sound, relative to some reference level. As a measure of sound intensity, a zero-decibel reference is stipulated to be the lowest level audible to the human ear.

## 1.6 Typical A-weighted Sound Power Levels from Construction Equipment




Source: CP 49: 1988

# Chapter 1

## Introduction

### 1.7 Behaviour of Noise in Windy Conditions



Source: <http://citysoundproofing.com/environ.html>

Noise travelling in the direction of wind will propagate further than expected while noise travelling against direction of wind will propagate lesser than expected.


## Chapter 2

### Introduction to Noise Management on site

#### 1.8 Equivalent Continuous Sound Level (Leq)

The definition of Leq is the measure used to express the average sound level (typically expressed in dBA) over a given period of time.

Therefore “Leq 5 mins” is the average sound level measured over 5 minutes etc.



Source:

<http://digital.ni.com/public.nsf/allkb/FCE0EC0A6B193A028625722E006DE298>

## Chapter 2

### Introduction to Noise Management on site

Effective management of noise pollution helps to maintain a good living environment for all.

As LTA continues to deliver more rail and road networks, construction sites are increasingly located in close proximity to residential, hospital, health care and school buildings. It is vital for contractors and LTA project teams to adopt a holistic approach towards noise management.

This guidebook will introduce **5 steps** that will help to achieve good noise management on site.

**Step 1** outlines the legislation and other regulatory requirements that relates to the control of noise pollution on site.

This will be covered in Chapter 3.

**Step 2** assists in identifying the various Noise Sensitive Receivers (NSR) and noise sources from construction activities. This will be covered in Chapter 4 & 5.

**Step 3** demonstrates means of managing and mitigating noise from construction activities.

This will be covered in Chapter 6 & 7.

## Chapter 2

### Introduction to Noise Management on site

**Step 4** summarises the process of noise monitoring required before and during construction works.


This will be covered in Chapter 8.

**Step 5** highlights different ways of effective communication and emphasises the importance of establishing good relationship with stakeholders.

This will be covered in Chapter 9.

This page is deliberately left blank

# Step 1: Meeting Regulatory and Other Requirements







## Chapter 3

### Regulatory and Other Requirements

#### 3.1 Permissible Construction Noise Limits

For Worksites within 150m from Existing Residential Premises

**For Monday to Saturday:**

| Types of affected buildings   | 7am - 7pm               | 7pm – 10pm             | 10pm – 7am             |
|---|-------------------------|------------------------|------------------------|
| (a) Hospital, schools, institutions of higher learning, homes for aged sick, etc. | 60 dBA<br>(Leq* 12 hrs) | 50 dBA<br>(Leq 12 hrs) |                        |
|   | 75 dBA<br>(Leq 5 mins)  | 55 dBA<br>(Leq 5 mins) |                        |
| (b) Residential buildings located less than 150m from the construction site       | 75 dBA<br>(Leq 12 hrs)  | 65 dBA<br>(Leq 1 hr)   | 55 dBA<br>(Leq 1 hr)   |
|   | 90 dBA<br>(Leq 5 mins)  | 70 dBA<br>(Leq 5 mins) | 55 dBA<br>(Leq 5 mins) |
| (c) Buildings other than those in (a) and (b) above                               | 75 dBA<br>(Leq 12 hrs)  | 65 dBA<br>(Leq 12 hrs) |                        |
|   | 90 dBA<br>(Leq 5 mins)  | 70 dBA<br>(Leq 5 mins) |                        |

\* Equivalent continuous noise level over the specified period, i.e. 5 mins, 1 hr or 12 hrs.



## Chapter 3

### Regulatory and Other Requirements

Note: Only applicable for sites given approval by NEA to work on Sundays/PH only.

| Types of affected buildings   | 7am - 7pm               | 7pm – 10pm             | 10pm – 7am |
|---|-------------------------|------------------------|------------|
| (a) Hospital, schools, institutions of higher learning, homes for aged sick, etc. | 60 dBA<br>(Leq* 12 hrs) | 50 dBA<br>(Leq 12 hrs) |            |
|   | 75 dBA<br>(Leq 5 mins)  | 55 dBA<br>(Leq 5 mins) |            |
| (b) Residential buildings located less than 150m from the construction site       | 75 dBA<br>(Leq 12 hrs)  | -                      | -          |
|   | 75 dBA<br>(Leq 5 mins)  | 55 dBA<br>(Leq 5 mins) |            |
| (c) Buildings other than those in (a) and (b) above                               | 75 dBA<br>(Leq 12 hrs)  | 65 dBA<br>(Leq 12 hrs) |            |
|   | 90 dBA<br>(Leq 5 mins)  | 70 dBA<br>(Leq 5 mins) |            |

\* Equivalent continuous noise level over the specified period, i.e. 5 mins, 1 hr or 12 hrs.



## Chapter 3

### Regulatory and Other Requirements

#### No Work Rule on Sundays and Public Holidays

On top of the permissible noise limits, NEA has also mandated a prohibition of work on Sundays and Public Holidays (PH) for construction sites located within 150m away from residential premises and noise sensitive premises.

The requirements are as follows:

- a) Site Established\* from 1 Sep 2010  
No work allowed from 10.00pm on Sat/eve of PH to 10.00am on Sun/PH
- b) Site Established\* from 1 Sep 2011  
No work allowed from 10.00pm on Sat/eve of PH to 7.00am on the following Mon/day after the PH

\* - Establishment of site is based on the BCA Permit to Commence Structural Works



## Chapter 3

### Regulatory and Other Requirements

#### 3.1.1 Correction Factor

The adjusted value for the maximum permissible noise level shall be obtained by adding the correction factor (in the table shown below) to either:

- The maximum permissible noise level (shown in the previous tables) **or**
- The baseline noise level.

Whichever is higher of the 2 noise levels.


| Difference between 2 noise levels in decibels (A) | Correction factor in decibels (A) |
|---|-----------------------------------|
| <b>Below 2</b>                                    | 3                                 |
| <b>2 to less than 4</b>                           | 2                                 |
| <b>4 to less than 10</b>                          | 1                                 |
| <b>10 and above</b>                               | 0                                 |



## Chapter 3

### Regulatory and Other Requirements

#### Adjusted Permissible Noise Level Using Correction Factor (Working Example)



Difference between **baseline noise** and **permissible noise level**,

$$91 - 90 = 1 \text{ dBA}$$


Using the **Correction Factor Table**, difference of 1dBA gives you a correction factor of **3dBA**.



## Chapter 3

### Regulatory and Other Requirements

Add the correction factor to either baseline noise level or prescribed permissible noise level. Whichever is higher.



As adjusted permissible noise level is now **94 dBA**. Construction noise level of 93 dBA still complies with the regulation.



## Chapter 3

### Regulatory and Other Requirements

#### 3.1.2 Penalties for Exceeding Permissible Limits

- The maximum fine for violating the permissible noise limits will be up to \$40,000 for court prosecutions
- The penalty for a continuing offence after conviction will be \$1,000 for every day the offence is continued



## Chapter 3

### Regulatory and Other Requirements

#### 3.2 CP 49:1998 Code of Practice for Noise Control on Construction and Demolition Sites

This section shall only highlight the salient points, for full details, please refer to CP 49.

##### **At Planning Stage**

- Consider processes, machineries and equipment required for different phases of operations
- Reduce noisy operations wherever feasible
- Noisy operations should start in the late morning and end by early afternoon
- Wherever possible, choose quieter techniques/ methods
- Expected level of construction noise should be determined





## **Chapter 3**

### **Regulatory and Other Requirements**

#### **At Design Stage**

- Identify NSRs
- Consider site layout to limit noise propagation
- Apply noise restriction if any
- Preferred off-site vehicle routes should be established to avoid NSRs

#### **At Tender Stage**

- Provision for noise control and monitoring should be included in tender documents
- Tenderer is expected to use best practicable means to minimise noise and satisfy himself of being able to comply with the permissible limits before submitting a tender



## Chapter 3

### Regulatory and Other Requirements

#### During Works

- Contractors should have a programme of works taking into account the site layout to minimise noise
- Implement specific measures to mitigate noise
- Adopt the use of quieter plant and equipment
- Ensure that all machineries are working properly
- Plan the hours of work and consider the effects on the neighbourhood and persons working on site
- Regularly monitor noise levels on site



## Chapter 3

### Regulatory and Other Requirements

#### 3.3 LTA General Specifications

##### **General Requirements (February 2013 Edition)**

This section shall only highlight the salient points, for full details, please refer to Annex A-F: Environmental Considerations of LTA General Specifications.

##### General

- Contractors shall appoint an acoustic consultant to prepare a noise management plan (NMP)
- Prior to the commencement of any construction activities and major diversion works, the Contractor shall carry out a pre-construction baseline noise monitoring for a duration of 1 week. The survey period shall include at least a weekday and a weekend
- NMP shall make reference to the Environmental Impact Assessment (EIA), be site-specific and in accordance to the respective construction phases
- NMP shall be submitted for acceptance before implementation of mitigation measures, which includes the use of full acoustic enclosures to the affected worksites



## Chapter 3

### Regulatory and Other Requirements

- NSRs must be identified
- Noisy plant, equipment and methods producing excessive noise will not be allowed to be used on site
- LTA has the right to stop any noisy activities during the school examination periods if work is in the vicinity of affected educational institutions
- It is the Contractor's responsibility to ensure that all machinery/equipment are maintained and operating to the standards indicated in their respective specifications



## Chapter 3

### Regulatory and Other Requirements

#### Noise Measurement

- The Contractor shall provide competent and qualified personnel and suitable equipment for measurements and recordings of noise levels
- Noise measurements will be required for buildings within 150m from the boundary of the construction site
- Measurements shall be carried out 1m away from the nearest façade of the building facing the site and readings shall be taken from at least 3 different levels at least 1.5m above grade without any obstruction/obstacles in direction of measurement
- Continuous noise monitoring shall be carried out for works within vicinity of NSRs
- At any time during the contract period as directed by the Engineer and after the project is completed and opened to traffic, the noise survey or part of it shall be repeated to establish any change in the noise levels



## Chapter 3

### Regulatory and Other Requirements

#### Noise Control

- All machinery and plant must be sound reduced prior to entering the site
- Contractor shall use power supplied by PowerGrid whenever possible
- No piling works will be allowed from 10pm to 7am unless both machinery and method are of a quiet nature
- Full length noise barriers must be at least 10m in height or break the line of sight from receiver to noise source. Noise barriers shall be erected at site boundaries facing NSRs
- Slurry treatment plants and launch shafts shall be housed within a full acoustic enclosure
- Noisy activities must be barricaded with portable sound barriers/panels
- All machinery in operation must have their covers properly shut at all times
- All plant/machinery/equipment must be pasted with a weather-proof sticker clearly indicating its noise emission level (at source) under normal operating condition



## Chapter 3

### Regulatory and Other Requirements

- Noise barriers should be erected before any work commences if the site is within proximity to residences and/or sensitive buildings or as directed by the Engineer
- Preparation for traffic diversion should be carried out during the day and portable acoustic panels/ enclosure must be deployed for such works
- The Contractor shall commit sufficient effort and time into public relation works to establish good rapport with the community. Such activities shall be subject to the Authority's approval



## Chapter 3

### Regulatory and Other Requirements

#### 3.4 NEA requirements

##### Submissions

At the start of a project, the following submissions shall be drafted and sent to NEA for their concurrence.

The submissions include:

- i. Proposed adjusted noise limits<sup>1</sup>
- ii. Construction NMP<sup>2</sup>

Subsequently, a presentation of the contract's NMP for NEA's concurrence will be required. This is to be carried out before commencement of works, start of a construction phase or change of site location.

##### Updates

For each project, LTA and Contractors' management shall meet NEA on an annual basis or as and when required to :

- Update NEA on upcoming works
- Inform residents that they may be potentially affected by noise
- Implement intended mitigation measures

1. Refer to Chapter 6.2 for method for measuring baseline noise level

2. Refer to Chapter 6 for guidelines on writing an NMP





## Chapter 3

### Regulatory and Other Requirements

#### Inspections

Joint inspections (ad-hoc) by LTA and NEA will be carried out once every 2 months or as and when required for NEA officers to appreciate the site conditions and assess the adequacy of measures implemented.

#### Emergency and Scheduled Road Works occurring at night

For Scheduled Road Works, the following shall be carried out:

- I. Notification shall be sent out to NEA call centre at least one week before planned works
- II. Public relation (PR) works carried out for nearby residences informing them of upcoming works
- III. Noise mitigating measures, such as noise barriers, to be erected to minimise noise disturbance



## Chapter 3


### Regulatory and Other Requirements

For Emergency works, the following shall be carried out:

- I. Notification shall be made to NEA call centre  
before commencement works
- II. Public relation (PR) works carried out for nearby residences informing them of upcoming works
- III. Install noise mitigating measures as and when available and reasonable

This page is deliberately left blank

## Step 2: Identification of Noise Sensitive Receivers & Noise Sources





## Chapter 4

### Noise Sensitive Receivers

#### 4.1 Noise Sensitive Receivers

Below are some examples of NSRs that are adjacent to some of LTA's construction site:



**Residential premises located less than 150m from construction site**

*C935: Located close to residential building*



**Hospitals**

*C920 & C921: Located near KKH*



## Chapter 4

### Noise Sensitive Receivers



**Homes for the aged,  
sick, etc**

*ER368: Located near to  
Ju Eng Home for Senior  
Citizens*

Source: <http://web.singnet.com.sg/~thamwong/project.html>



**Places of Worship**

*C923: Located in close  
proximity to a church*



## Chapter 4

### Noise Sensitive Receivers



#### **Schools, Institutes of higher learning**

*C918: In the  
boundaries of Hwa  
Chong Institution*



#### **Public Libraries**

*C925A: Located  
near to a public  
library*

Source: <http://static.panoramio.com/photos/iw-thumbnail/20191930.jpg>



## Chapter 4

### Noise Sensitive Receivers



#### Commercial Areas

*C922: Located near UE Bizhub East commercial building*



#### Hotels and Serviced Apartments

*C936: Located near to Hotel Rendezvous*





## Chapter 4

### Noise Sensitive Receivers

**Other noise sensitive receivers to take note:**



**Association of the Visually Handicapped**



## Chapter 5

### Noise Sources on Construction Sites

#### 5.1 Overview of Noise Sources on Construction Sites

A typical construction site has equipments and work processes that generate noise.

The following table shows a general guide to the risk of annoyance of different levels of loudness of noise and the type of noise generated by these noise sources. Noise levels taken at source.

| Noise Output<br>Type of noise | High | Medium | Low    |
|-------------------------------|------|--------|--------|
| Steady Noise                  | HIGH | MEDIUM | LOW    |
| Fluctuating Noise             | HIGH | MEDIUM | LOW    |
| Impact/Impulse Noise          | HIGH | HIGH   | MEDIUM |

| Noise Output | General definition   |
|--------------|--|
| High         | Predicted noise levels are more than 3 dB above the statutory limits |
| Medium       | Predicted noise levels are up to 3 dB above the statutory limits     |
| Low          | Predicted noise levels are below or at statutory limits              |


Source: ERM, 2012




## Chapter 5

### Noise Sources on Construction Sites

**Steady Noise** is noise with negligibly small fluctuations of level and has frequencies evenly distributed throughout the audible range. E.g. Noise from generator set, ventilation fans, mechanical hacking etc.



**Fluctuating noise** is noise whose level varies continuously and to an appreciable extent. It consists of a wide mixture of frequencies. E.g. Noise from vehicle movements, deep cement mixing (DCM) machines and overall construction noise.






## Chapter 5

### Noise Sources on Construction Sites

**Impact or Impulse Noise** is noise defined as a transient sound of duration of less than one second which may be repeated after a delay of more than one second. E.g. Noise from spinning and locking of bucket of bore piling machine, hammering of rebar cages etc.



Source: <http://www.mom.gov.sg/Documents/safety-health/Guidelines-for-Noise-Control-Vibration-Part2.pdf>



## **Chapter 5**

### **Noise Sources on Construction Sites**

#### 5.2 Noisy Plants and Equipments

The following are some examples of common plants and equipment found in LTA construction sites and the type of noise they emit.

Contractors should pay particular attention to plants and equipments with risk of annoyance labeled as high (red), they are to be shielded or located away from NSRs as much as possible.



## Chapter 5

### Noise Sources on Construction Sites

#### High Risk of Annoyance

- High noise output
- Steady noise source



Old generator sets

#### High Risk of Annoyance

- High noise output
- Fluctuating noise source



Power packs



## Chapter 5

### Noise Sources on Construction Sites

#### High Risk of Annoyance

- High noise output
- Steady noise source



Ventilation fans

#### Medium Risk of Annoyance

- Medium noise output
- Steady noise source



Idling vehicles



## Chapter 5

### Noise Sources on Construction Sites

#### Medium Risk of Annoyance

- Medium noise output
- Steady noise source



Desanding plant

#### Medium Risk of Annoyance

- Medium noise output
- Fluctuating noise source



Old machinery





## **Chapter 5**

### **Noise Sources on Construction Sites**

#### 5.3 Noisy Operations & Work Processes

Certain construction operations and methods generate high noise output that is of intermittent nature. These types of noise are also known as impact/impulse noise.

Contractors should pay particular attention to such operations as they are the reasons behind most complaints. Such operations and work processes are best scheduled in the day and to be accompanied with appropriate noise mitigation measures at all times.

The following are some examples of common construction work operations and their respective risk of annoyance.



## Chapter 5

### Noise Sources on Construction Sites

#### High Risk of Annoyance

- High noise output
- Impact/Impulse noise source



Mechanical hacking works

#### High Risk of Annoyance

- Medium noise output
- Fluctuating noise source



Diaphragm wall works



## Chapter 5

### Noise Sources on Construction Sites

#### High Risk of Annoyance

- High noise output
- Impact/Impulse noise source



Bored piling works

#### High Risk of Annoyance

- High noise output
- Impact/Impulse noise source



Demolition works



## Chapter 5

### Noise Sources on Construction Sites

#### High Risk of Annoyance

- High noise output
- Fluctuating noise source



Installation/Extraction of sheet piles

#### High Risk of Annoyance

- High noise output
- Fluctuating noise source



Installation/Extraction of casings



## Chapter 5

### Noise Sources on Construction Sites

#### Medium Risk of Annoyance

- Low noise output
- Impact/Impulse noise source



Washing bays

#### Medium Risk of Annoyance

- Medium noise output
- Fluctuating noise source



Deep cement mixing works



## Chapter 5

### Noise Sources on Construction Sites

#### Medium Risk of Annoyance

- Medium noise output
- Fluctuating noise source



Concreting works

#### Low Risk of Annoyance

- Low noise output
- Fluctuating noise source



Vehicular movement



## **Chapter 5**

### **Noise Sources on Construction Sites**

#### 5.4 Noisy Parts of Machinery

The following are some examples of noisy parts of machinery that can cause annoyance to nearby stakeholders if not addressed.

Machinery parts that produces noise at a high risk of annoyance (red), they are to be rectified or sent for maintenance as soon as possible. Mufflers or acoustic panels should be considered to be installed at noisy parts if noise persists after rectification.



## Chapter 5

### Noise Sources on Construction Sites

#### High Risk of Annoyance

- High noise output
- Steady noise source



Noise emission outlet

#### High Risk of Annoyance

- High noise output
- Steady noise source



Opened compartment cover





## Chapter 5

### Noise Sources on Construction Sites

#### High Risk of Annoyance

- High noise output
- Steady noise source



Reverberating cover


#### Medium Risk of Annoyance

- Medium noise output
- Fluctuating noise source



Poor maintenance of joints

## Step 3: Management and Mitigation






## Chapter 6

### Noise Management Plan

#### 6.1 Overview and Strategies for an Effective Noise Management Plan

The NMP is designed to help contractors estimate the noise impact and plan measures to ensure compliance with the construction permissible noise limits and to reduce noise nuisance to NSRs.

For an effective NMP, efforts for the reduction of noise shall be apportioned in the following order.



Last but not least, all these should be compiled to an NMP to be submitted. Details refer to Appendix 1&2.



## Chapter 6

### Noise Management Plan

#### 6.2 Overview of Baseline Noise Study

Prior to the commencement of work, pre-construction noise monitoring shall be carried out to establish the baseline noise level for the site.

**Step 1: Pre-construction** baseline noise monitoring to be carried out for **7 days** (i.e. Monday to Sunday).



Take note:  
**Acoustic Consultant** to take measurements and recordings of noise levels.

**Step 2: Following** the completion of a particular stage of works, noise survey is to be repeated to establish any change in the noise levels.

**Step 3: Continuous** noise monitoring shall be carried out for works within vicinity of NSRs throughout the project.



## Chapter 6

### Noise Management Plan

#### Step 4: Adjustment of permissible noise limits

Based on the baseline obtained, the acoustic consultant may recommend a set of proposed adjusted noise limits, which are to be submitted to NEA for approval.

The proposed adjusted noise limits shall be segregated into the follow time frames:

7am-7pm

7pm-10pm

10pm-12am

12am-7am



## Chapter 6

### Noise Management Plan

#### 6.3 Site Planning (Elimination Method)

3 items to consider when planning your site.

1. Referring but not limited to the recommendations in the Environmental Impact Assessment (EIA),
  - Identify the types of noise sensitive receivers (NSR) near to your site
  - Establish the methods of construction taking into consideration quieter alternatives
  - Establish the types of machinery to be used, giving a preference to new over older machines
2. Plan your site layout such that minimal disturbance reaches the NSRs
3. Schedule noisy activities to be carried out in the day




## Chapter 6

### Noise Management Plan

#### 6.3.1 Distancing

If there are no space constraints on site, distancing provides a free means of reducing noise. The reduction in noise levels depends primary on:

- type of noise source and
- distance between noise source and receiver.




Generally, every doubling of distance for a point source (e.g generator set) will reduce noise at the receiver's end by approximately 6dB.



## Chapter 6

### Noise Management Plan



Whereas, every doubling of distance for a linear source (e.g moving traffic) will reduce noise at the receiver's end by approximately 3dB.





## Chapter 6

### Noise Management Plan

#### 6.3.2 Site Layout

Make use of structures on site to act as a form of noise barrier.



Rows of silos placed before receivers aid in mitigating construction noise



Placing noisy plant behind large objects also helps in reducing noise

Source:

[http://www.streetdirectory.com/stock\\_images/travel/simg\\_show/12826430520298/1/lasalle\\_college\\_of\\_the\\_arts/](http://www.streetdirectory.com/stock_images/travel/simg_show/12826430520298/1/lasalle_college_of_the_arts/)



## Chapter 6

### Noise Management Plan

Plan vehicular access routes to ensure minimal disturbance to the nearby premises.



Control speed of moving vehicles to reduce noise



Speeding vehicles pose a threat to safety and generate both dust and excessive noise




## Chapter 6

### Noise Management Plan



Site washing bays and vehicular access located away from NSRs



Sudden jets of water are a form of intermittent noise that can startle residents, especially at night



## Chapter 6

### Noise Management Plan



Paved vehicular access route provides for a smoother drive



Muddy ground surface requires revving of engines which in turn produces noise



## Chapter 6

### Noise Management Plan



Designate a storage area and ensure proper stacking of materials



Retrieval and “dumping” of materials in a messy storage area creates noise



## Chapter 6

### Noise Management Plan

#### 6.4 Consider Alternatives (Substitution Method)

Consider the use of quieter machinery and methods of construction in your planning. For activities that are inherently noisy, try to schedule them in the day.



Pre-boring to crush hard rocks and aggregates for the ease of installing sheet pile



Use of quieter alternatives such as a silent piler for installing sheet piles



## Chapter 6

### Noise Management Plan



Traditional method of using vibro- hammer generates loud noise and ground vibration



Casing rotator used as a quieter alternative to bore piling works



## Chapter 6

### Noise Management Plan

#### 6.5 Mitigation Measures (Engineering Control)

##### 6.5.1 At Source

Mitigation of noise at source is the most effective way to reduce noise pollution. It thus makes sense to deploy the measures below as much as possible.



Use sound-reduced machinery



*Sound-proof generator set*



*Sound-proof welding set*



*Welding set with noise level verified on-site and displayed*





## Chapter 6

### Noise Management Plan



Avoid the use of old machinery



*Old excavators*



*Old air compressors*



## Chapter 6

### Noise Management Plan



By adding a layer of acoustic material to metal sheets such as machinery cover can help to reduce reverberating noise



## Chapter 6

### Noise Management Plan



By placing vibrating units on isolators such as a coil of spring can reduce noise generated by vibration



Noise shield around rotary head



## Chapter 6

### Noise Management Plan



For machines that are not yet sound-reduced, install noise panels at noise emission outlets



Panels installed at noise emission outlets should be longer or curved at the end to shield off angles that allow noise to escape



## Chapter 6

### Noise Management Plan



Noise panels are closely aligned in order to effectively reduce engine noise from source



Missing noise panels will allow noise generated from machinery to escape



## Chapter 6

### Noise Management Plan



Noise Shield for Pile Driving Hammer



Rubber Padding on boom frame to avoid sharp noise when wire ropes hit against it



## Chapter 6

### Noise Management Plan



Cantilever noise barrier to shield noise generated from ventilation fans



Acoustic material is not closely aligned to effectively reduce noise generated from ventilation fans



## Chapter 6

### Noise Management Plan



Boring rig with butterfly bucket to reduce noise generated from the spinning and locking of bucket head





## Chapter 6

### Noise Management Plan

#### 6.5.2 Using Enclosures

Enclosures also offer a good way of noise reduction by minimising outlets where noise can escape from. Thus a full enclosure is more effective than a partial enclosure. The choice of using which depends on several factors such as:

- Mobility of noisy plant/ equipment
- Operational method of plant/ equipment
- Availability of noise panels
- Whether personnel are required to work within the enclosure
- Location of noisy plant/ equipment
- Cost of installing the enclosure



## Chapter 6

### Noise Management Plan



Partial enclosures if used, should be oriented such that openings are facing away from NSRs and if there's no roof, it should not be placed below any tall residential buildings



Housing of small motor units



## Chapter 6

### Noise Management Plan



Using full enclosure  
for housing of  
generator set



Access to enclosed  
generator set  
should remained  
closed when not  
in use



## Chapter 6

### Noise Management Plan



Noisy parts of cranes are enclosed using noise panels



## Chapter 6

### Noise Management Plan



Noise enclosures for D-wall machine



## Chapter 6

### Noise Management Plan



Noise enclosures for desanding plant



## Chapter 6

### Noise Management Plan



Noise enclosure for  
launch shaft



## Chapter 6

### Noise Management Plan

#### 6.5.3 At Transmission Path

Noise barriers deployed this way are usually placed in between the noise source and receiver to force noise to travel over a greater distance and/or be absorbed by the acoustic materials, thus decreasing in loudness by the time it reaches the receiver.



Install noise barriers on top and along the length of hoardings where required



Noise barriers should be installed before any construction work starts





## Chapter 6

### Noise Management Plan



Absence of noise barriers means NSRs will receive direct noise impact from construction work



Noise barriers are installed once site hoardings are up



## Chapter 6

### Noise Management Plan



Use of double-layer noise barrier to reduce noise along transmission path



As much as possible, noise barriers should block the line of sight of low-rise NSRs



## Chapter 6

### Noise Management Plan



Noise barriers  
erected on top of  
site gate



Noise barrier  
panels mounted  
on site gate



## Chapter 6

### Noise Management Plan



Noise curtain may be used to replace traditional stiff noise panels to act as perimeter noise barrier if the site is located in very close proximity to NSRs





## Chapter 6

### Noise Management Plan



Portable noise barriers can be used at the face of operations for noisy activities



Portable noise barriers should be placed in front of the noise emission source



## Chapter 6

### Noise Management Plan



Portable noise barriers should follow noisy operations and not remain in the previous location



Portable noise barriers used to shield noisy parts of machinery for scheduled road works at night



## Chapter 6

# Noise Management Plan



Use of air-inflatable noise barrier to shield noisy activities





## Chapter 6

### Noise Management Plan

Alternatives to noise panels used to shield noise from construction site.



Acoustic curtain used as portable noise barriers to shield noisy diaphragm wall activities





## Chapter 6

### Noise Management Plan



Position noisy generators behind a row of noise barriers



Do not place noisy generators with their noise emission outlets facing NSRs



## Chapter 6

### Noise Management Plan



#### Noise Mitigation Measures at Transmission Path:

Portable air-inflated noise barriers used at the face of operations for diaphragm wall activities



#### Using of Enclosures:

Noise enclosure used to block noise from noisy part of machinery



## Chapter 6

### Noise Management Plan

#### 6.6 Procedures, Awareness and Training (Administrative Control)

##### 6.6.1 Behavioural Improvement

In order to reduce high pitch noise which could cause generate annoyance in the nearby residents, simple techniques can be employed to reduce such noises.



Wrap one of the resonance head with cloth to reduce high pitch noise



Wrap hammers with cloth to reduce tonal noise generated from the knocking of rebars



## Chapter 6

### Noise Management Plan



Make use of rubber mallets in place of hammers while working at night



Educate workers to lay rebar down properly instead of dropping them from a standing position



## Chapter 6

### Noise Management Plan



Remind drivers  
not to leave their  
engines idling  
when not in use



Remind machine  
operators not  
to exert more  
power than  
necessary during  
operations



## Chapter 6

### Noise Management Plan



Conduct briefing for workers on the correct methods of handling of machine/material/working methods and personal conduct in order to reduce noise generated on site



## Chapter 6

### Noise Management Plan

#### 6.6.2 Regular maintenance



Machinery should be regularly maintained by certified personnel



## Chapter 6

### Noise Management Plan

#### 6.6.3 At Receivers' End



Adhering acoustic materials to the windows and doors of NSRs to reduce noise transmitted indoors




Planting trees at NSRs do not actually reduce noise much but they provide a psychological soothing effect





## Chapter 6

### Noise Management Plan



Installing double-glazed glass at NSRs could be an option for commercial businesses, such as hotels. However, if intended for residential premises, do consider factors such as cost of installing double-glazed glass and loss of natural ventilation. Additional expenses may also be incurred due to installation of air-conditioner units and their operating cost.



## Chapter 7

### Basic Principles of Using Noise Barriers

#### 7.1 Orientation

The side of noise barrier with louvers shall face the noise source.



The flat side of the noise barrier should be facing the noise recipient.





## Chapter 7

### Basic Principles of Using Noise Barriers

#### 7.2 Alignment

Noise panels must be closely aligned in order to be efficient.



Misaligned panels will allow noise to seep through gaps.





## Chapter 7

### Basic Principles of Using Noise Barriers

#### 7.3 Acoustic Properties of Materials

| Material   | Thickness<br>mm | Surface Density<br>kg/m <sup>2</sup> | Transmission<br>Loss * (TL) dB |
|--|-----------------|--------------------------------------|--------------------------------|
| Polycarbonate  | 8-12            | 10-14                                | 30-33                          |
| Acrylic [Poly-Methyl-Meta- Acrylate (PMMA)]                    | 15              | 18                                   | 32                             |
| Concrete Block 200x200x400 light weight                        | 200             | 151                                  | 34                             |
| Dense concrete   | 100             | 244                                  | 40                             |
| Light concrete   | 150             | 244                                  | 39                             |
| Light concrete   | 100             | 161                                  | 36                             |
| Brick  | 150             | 288                                  | 40                             |
| Steel, 18 ga   | 1.27            | 9.8                                  | 25                             |
| Steel, 20 ga   | 0.95            | 7.3                                  | 22                             |
| Steel, 22 ga   | 0.79            | 6.1                                  | 20                             |
| Steel, 24 ga   | 0.64            | 4.9                                  | 18                             |
| Aluminium Sheet  | 1.59            | 4.4                                  | 23                             |
| Aluminium Sheet  | 3.18            | 8.8                                  | 25                             |
| Aluminium Sheet  | 6.35            | 17.1                                 | 27                             |
| Wood   | 25              | 18                                   | 21                             |
| Plywood  | 13              | 8.3                                  | 20                             |
| Plywood  | 25              | 16.1                                 | 23                             |
| Absorptive panels with polyester film backed<br>by metal sheet | 50-125          | 20-30                                | 30-47                          |

\* Values assuming no openings or gaps in the barriers.

Source:

[http://www.epd.gov.hk/epd/english/environmentinhk/noise/guide\\_ref/design\\_barriers\\_content2.html](http://www.epd.gov.hk/epd/english/environmentinhk/noise/guide_ref/design_barriers_content2.html)

The values listed in the table is meant to be estimates only. For noise reduction, the maximum value that can be achieved theoretically is approximately 20dB.



## Chapter 7

### Basic Principles of Using Noise Barriers

#### 7.4 Efficiency

| % area occupied by leaks           | Transmission Loss without leaks at 500 Hz |       |       |       |
|------------------------------------|---|-------|-------|-------|
|                                    | 10dB*                                     | 15dB* | 20dB* | 25dB* |
| reduction in transmission loss, dB |   |       |       |       |
| 50                                 | 10+                                       | 15+   | 20+   | 25+   |
| 25                                 | 10  | 15    | 20    | 25    |
| 13                                 | 8   | 12    | 17    | 22    |
| 6                                  | 5   | 10    | 14    | 19    |
| 3                                  | 4   | 7     | 11    | 16    |
| 1.5                                | 2   | 5     | 9     | 13    |
| 0.78                               | 1   | 3     | 6     | 10    |
| 0.39                               | 1   | 2     | 4     | 8     |
| 0.20                               | 0   | 1     | 3     | 5     |
| 0.10                               | 0   | 1     | 1     | 4     |
| 0.05                               | 0   | 0     | 1     | 2     |

Source:

[http://www.epd.gov.hk/epd/english/environmentinhk/noise/guide\\_ref/design\\_barriers\\_content2.html](http://www.epd.gov.hk/epd/english/environmentinhk/noise/guide_ref/design_barriers_content2.html)

The above table shows you the relationship between gaps and effectiveness of noise barriers. The area shaded in darker colour indicates a detectable loss in efficiency of the noise barriers as a result of the corresponding percentage area occupied by leaks.



## Chapter 7

### Basic Principles of Using Noise Barriers

#### 7.5 Dimensions



Noise panels must be considerably longer than the length of building they are trying to shield



Noise barriers should be built higher for better performance

However, thoughts need to be given to structural and wind load requirements



## Chapter 7

### Basic Principles of Using Noise Barriers

#### 7.5 Dimensions



To overcome structural and wind load, tall noise barriers may be supported on I-beams.


The arrangement reduces the tie-back area required



Example of high noise barriers built to shield residents in low-rise buildings from noise

The general rule of thumb when using noise barriers, is to break the line of sight of the source from the receiver.

## Step 4: Noise Monitoring








## Chapter 8

### Noise Monitoring

#### 8.1 Noise monitoring

There are 3 types of noise monitoring which should be carried out:



*Note: Images are for illustration purposes only*



## Chapter 8

### Noise Monitoring

## 8.2 Noise Meters

Noise monitoring must be carried out using a Type 1 noise meter conforming to the IEC 61672 (BS EN 61672), IEC 60651 (BS EN 60651) or IEC 60804 (BS EN 60804) standards or other equivalent standards.



The monitoring instrument should comprise of:

- An integrating-averaging sound level meter set to frequency weighting A
- A sound exposure level meter
- A sound level meter set to frequency-weighting A and time-weighting S
- A data logger for sampling the running value of A-weighted sound pressure level
- A statistical distribution analyser for sampling running value of A-weighted sound pressure level



## Chapter 8

### Noise Monitoring

#### 8.3 Pre-construction Noise Monitoring

Baseline noise levels shall be established according to method stated in Chapter 6.2.

Noise Simulation of the existing environment shall also be carried out to determine the noise level experienced by the surrounding NSRs. Appropriate noise mitigation measures may then be applied to reduce noise levels to within permissible limits.





## Chapter 8

### Noise Monitoring

#### 8.4 Continuous monitoring during construction phase

Continuous noise monitoring must be carried out for the entire duration of the project as long as there are any NSRs within 150m from the construction site. This form of permanent noise monitoring must be located at the nearest affected building and its location must be acknowledged by the relevant authority.

Noise meters shall be located 1m away from the nearest façade of the building facing the site, 1.5m above at-grade level without any obstructions/obstacles in the direction of measurement.



*Noise meter  
located in front of  
public library*



## Chapter 8

### Noise Monitoring

For tall buildings such as a HDB block, it is recommended that the location for noise monitoring be located at least 3 different levels of the building. (1st storey, intermediate storey and top storey).



This system shall be equipped with a SMS “alert” feature to send out alerts when permissible limits are exceeded.



## Chapter 8

### Noise Monitoring


#### 8.5 Ad-hoc monitoring

Ad-hoc noise monitoring must be carried out by competent personnel whenever work progresses into the night, weekends or during noisy operations. Once noise levels are approaching permissible limits, the person-in-charge of site should be notified so that additional measures can be adopted to reduce disturbance to the nearby NSRs.



This page is deliberately left blank

## Step 5: Community Engagement







## Chapter 9

### Public Relations Work

#### 9.1 Overview of Public Relations Work

The integration of public relations as part of an overall noise management strategy is growing in importance today. As a person's acceptance of noise level is dependent on an individual's tolerance, it is important to include public relation works together with the use of engineering technologies.

Good public relation works would:

- Allow public to better understand our works
- Gain and build public's trust
- Open up communication channels
- Allow faster resolution of problems



## Chapter 9

### Public Relations Work

Below are some situations that could decrease the public's trust and their tolerance level to noise:

- Where there is originally low ambient noise level
- Intermittent, impulsive, startling noise
- Low frequency noise that causes vibrations in any parts of the building structure
- Any changes/ fluctuation in noise patterns
- Noise created at time nearing/ during rest hours



## Chapter 9

### Public Relations Work

#### 9.2 Examples of Public Relations Work



Organise regular community bonding/ information sharing sessions with the residents & grassroots



Regular publication of newsletters to keep residents informed on our development



## Chapter 9

### Public Relations Work



Inform the relevant authority in advance of any anticipated night works



Discuss noise mitigation with the relevant authority before the commencement of works



Distribute circulars to residents and stakeholders in advance of any anticipated night works



## Chapter 9

### Public Relations Work



Carry out engagement with schools and institutions of higher learning



Making use of multimedia resources to engage stakeholders



## Chapter 9

### Public Relations Work




Project information centre for engagement of stakeholders

This page is deliberately left blank



## Appendix 1

### Flowchart for the Process on Noise Management








## Appendix 1

### Flowchart for the Process on Noise Management





## Appendix 2

### Format of report for Noise Management Plan

#### Report format of a Noise Management Plan

At the start of the project, the contractor shall submit to LTA and NEA a Noise Management Plan. The NMP shall contain but not limited to the following sections.

1. Project information and relevant contact numbers
2. Baseline noise monitoring and locations of noise meters
3. Adjusted permissible noise limits
4. Identification of nearby sensitive premises
5. Site layout with locations of equipment
6. Schedule of work demonstrating consideration of noisy activities
7. List of powered equipment and their noise emission levels
8. Noise assessment including total anticipated noise emission levels
9. Noise mitigation measures with estimated noise reduction levels
10. Public relations strategies
11. Supporting documents (i.e. site map, photographs, equipment certificates etc)



## Appendix 3

### Useful Information

It is possible to estimate the sound power level (SPL) at the receiver's end using this theoretical formula:

$$L_{p(A)} = L_{w(A)} - 20 \log_{10} R - 8$$

where:

$L_{p(A)}$  = SPL at receiver's end dB(A)

$L_{w(A)}$  = SPL at source dB(A) and

R = distance from source to receiver's end (metres)

This calculation assumes that:

- Sound is radiated uniformly in all directions
- Terrain is that of a flat, open ground
- No obstacle between source and receiver
- Do not take into consideration effect of reflected sound from building facade



## Appendix 3

### Useful Information

A list of estimated SPL at receiver's end has been calculated for your convenience and is meant to serve only as a guide:

| SPL at source dB (A) | Estimated SPL dB(A) at a distance R from source |       |       |       |       |       |
|----------------------|---|-------|-------|-------|-------|-------|
|                      | R=20m   | R=30m | R=40m | R=50m | R=60m | R=70m |
| 80                   | 46.0  | 42.5  | 40.0  | 38.0  | 36.4  | 35.1  |
| 81                   | 47.0  | 43.5  | 41.0  | 39.0  | 37.4  | 36.1  |
| 82                   | 48.0  | 44.5  | 42.0  | 40.0  | 38.4  | 37.1  |
| 83                   | 49.0  | 45.5  | 43.0  | 41.0  | 39.4  | 38.1  |
| 84                   | 50.0  | 46.5  | 44.0  | 42.0  | 40.4  | 39.1  |
| 85                   | 51.0  | 47.5  | 45.0  | 43.0  | 41.4  | 40.1  |
| 86                   | 52.0  | 48.5  | 46.0  | 44.0  | 42.4  | 41.1  |
| 87                   | 53.0  | 49.5  | 47.0  | 45.0  | 43.4  | 42.1  |
| 88                   | 54.0  | 50.5  | 48.0  | 46.0  | 44.4  | 43.1  |
| 89                   | 55.0  | 51.5  | 49.0  | 47.0  | 45.4  | 44.1  |



## Appendix 3

### Useful Information

| SPL at source dB (A) | Estimated SPL dB(A) at a distance R from source |       |       |       |       |       |
|----------------------|---|-------|-------|-------|-------|-------|
|                      | R=20m   | R=30m | R=40m | R=50m | R=60m | R=70m |
| 90                   | 56.0  | 52.5  | 50.0  | 48.0  | 46.4  | 45.1  |
| 91                   | 57.0  | 53.5  | 51.0  | 49.0  | 47.4  | 46.1  |
| 92                   | 58.0  | 54.5  | 52.0  | 50.0  | 48.4  | 47.1  |
| 93                   | 59.0  | 55.5  | 53.0  | 51.0  | 49.4  | 48.1  |
| 94                   | 60.0  | 56.5  | 54.0  | 52.0  | 50.4  | 49.1  |
| 95                   | 61.0  | 57.5  | 55.0  | 53.0  | 51.4  | 50.1  |
| 96                   | 62.0  | 58.5  | 56.0  | 54.0  | 52.4  | 51.1  |
| 97                   | 63.0  | 59.5  | 57.0  | 55.0  | 53.4  | 52.1  |
| 98                   | 64.0  | 60.5  | 58.0  | 56.0  | 54.4  | 53.1  |
| 99                   | 65.0  | 61.5  | 59.0  | 57.0  | 55.4  | 54.1  |



## Appendix 3

### Useful Information

| SPL at source dB (A) | Estimated SPL dB(A) at a distance R from source |       |       |       |       |       |
|----------------------|---|-------|-------|-------|-------|-------|
|                      | R=20m   | R=30m | R=40m | R=50m | R=60m | R=70m |
| 100                  | 66.0  | 62.5  | 60.0  | 58.0  | 56.4  | 55.1  |
| 101                  | 67.0  | 63.5  | 61.0  | 59.0  | 57.4  | 56.1  |
| 102                  | 68.0  | 64.5  | 62.0  | 60.0  | 58.4  | 57.1  |
| 103                  | 69.0  | 65.5  | 63.0  | 61.0  | 59.4  | 58.1  |
| 104                  | 70.0  | 66.5  | 64.0  | 62.0  | 60.4  | 59.1  |
| 105                  | 71.0  | 67.5  | 65.0  | 63.0  | 61.4  | 60.1  |
| 106                  | 72.0  | 68.5  | 66.0  | 64.0  | 62.4  | 61.1  |
| 107                  | 73.0  | 69.5  | 67.0  | 65.0  | 63.4  | 62.1  |
| 108                  | 74.0  | 70.5  | 68.0  | 66.0  | 64.4  | 63.1  |
| 109                  | 75.0  | 71.5  | 69.0  | 67.0  | 65.4  | 64.1  |



## Appendix 3

### Useful Information

| SPL at source dB (A) | Estimated SPL dB(A) at a distance R from source |       |       |       |       |       |
|----------------------|---|-------|-------|-------|-------|-------|
|                      | R=20m   | R=30m | R=40m | R=50m | R=60m | R=70m |
| 110                  | 76.0  | 72.5  | 70.0  | 68.0  | 66.4  | 65.1  |
| 111                  | 77.0  | 73.5  | 71.0  | 69.0  | 67.4  | 66.1  |
| 112                  | 78.0  | 74.5  | 72.0  | 70.0  | 68.4  | 67.1  |
| 113                  | 79.0  | 75.5  | 73.0  | 71.0  | 69.4  | 68.1  |
| 114                  | 80.0  | 76.5  | 74.0  | 72.0  | 70.4  | 69.1  |
| 115                  | 81.0  | 77.5  | 75.0  | 73.0  | 71.4  | 70.1  |
| 116                  | 82.0  | 78.5  | 76.0  | 74.0  | 72.4  | 71.1  |
| 117                  | 83.0  | 79.5  | 77.0  | 75.0  | 73.4  | 72.1  |
| 118                  | 84.0  | 80.5  | 78.0  | 76.0  | 74.4  | 73.1  |
| 119                  | 85.0  | 81.5  | 79.0  | 77.0  | 75.4  | 74.1  |



## Appendix 3

### Useful Information

| SPL at source dB (A) | Estimated SPL dB(A) at a distance R from source |       |       |       |       |       |
|----------------------|---|-------|-------|-------|-------|-------|
|                      | R=20m   | R=30m | R=40m | R=50m | R=60m | R=70m |
| 120                  | 86.0  | 82.5  | 80.0  | 78.0  | 76.4  | 75.1  |
| 121                  | 87.0  | 83.5  | 81.0  | 79.0  | 77.4  | 76.1  |
| 122                  | 88.0  | 84.5  | 82.0  | 80.0  | 78.4  | 77.1  |
| 123                  | 89.0  | 85.5  | 83.0  | 81.0  | 79.4  | 78.1  |
| 124                  | 90.0  | 86.5  | 84.0  | 82.0  | 80.4  | 79.1  |
| 125                  | 91.0  | 87.5  | 85.0  | 83.0  | 81.4  | 80.1  |
| 126                  | 92.0  | 88.5  | 86.0  | 84.0  | 82.4  | 81.1  |
| 127                  | 93.0  | 89.5  | 87.0  | 85.0  | 83.4  | 82.1  |
| 128                  | 94.0  | 90.5  | 88.0  | 86.0  | 84.4  | 83.1  |
| 129                  | 95.0  | 91.5  | 89.0  | 87.0  | 85.4  | 84.1  |





## Appendix 3

### Useful Information

#### Pre-construction phase

Please score using the maximum marks given as a guide.

| No. | Pre-Construction Phase  | Scores     |
|-----|---|------------|
| 1   | Noise sensitive receivers near my site have been identified                       | 3          |
| 2   | We have considered the use of quieter construction methods                        | 3          |
| 3   | We have considered the use of sound-reduced and/or newer machinery                | 3          |
| 4   | We have scheduled noisy activities to be carried out in the day whenever possible | 3          |
| 5   | We have engaged an ECO as well as a PRO   | 2          |
| 6   | Pre-construction noise monitoring was carried out continuously for a week         | 3          |
| 7   | Noisy equipment are sited at a distance from the NSRs                             | 3          |
| 8   | Large structures/ natural barriers on site are used as noise barriers             | 2          |
| 9   | There is a speed limit for vehicles moving through our site                       | 2          |
| 10  | Vehicular access route is paved   | 2          |
| 11  | Washing bays and vehicular access points are sited away from NSRs where possible  | 2          |
| 12  | There is a proper stacking system for storage and rebar work areas                | 2          |
|     | <b>Total score</b>  | <b>/30</b> |



## Appendix 3

### Useful Information

#### Score Results

Total possible marks for this section = 30 marks

| If your score falls in the range of: | Status    | Remarks   |
|--------------------------------------|-----------|---|
| < 15                                 | Poor      | You have to put more thoughts into your site planning. A quiet site requires a good site layout and provisions for noise mitigation measures and quieter machinery to effectively reduce noise. |
| 15 - 25                              | Average   | You probably have considered most of the elements in achieving a quieter site. Try improving by extending the considerations to more activities and machinery.                                  |
| > 25                                 | Excellent | Well done! You have thought through all major work activities and machinery needed for your work. Just remember to implement them when construction works commence!                             |



## Appendix 3

### Useful Information

#### Construction phase

| No. | Construction Phase   | Scores     |
|-----|--|------------|
| 1   | Noise barriers are installed immediately after site hoardings are up   | 5          |
| 2   | Noisy machinery are fitted with noise panels at the side   | 5          |
| 3   | Loose attachments on the machine have been secured or removed  | 3          |
| 4   | Stationary equipment are housed in enclosures  | 5          |
| 5   | Covers of machinery are kept closed when in operation  | 3          |
| 6   | Idling vehicles have their engines switched off  | 3          |
| 7   | Machinery are serviced regularly   | 5          |
| 8   | Portable noise barriers are used at face of noisy operations and are redeployed as the work progresses           | 5          |
| 9   | Machine operators and workers have been briefed on quieter working techniques                                    | 5          |
| 10  | Noise barriers installed are able to break the line of sight between noise source and receiver                   | 5          |
| 11  | A Type 1 Noise meter conforming to IEC/ BS EN 60651/60804 or equivalent standards is used for monitoring purpose | 3          |
| 12  | Monitoring is carried out at the nearest affected NSR  | 5          |
| 13  | Exact location of monitoring has been acknowledged by the relevant authority                                     | 5          |
| 14  | Ad-hoc monitoring is carried out for night works   | 3          |
|     | <b>Total</b>   | <b>/60</b> |



## Appendix 3

### Useful Information

#### Score Results

Total possible marks for this section = 60 marks

| If your score falls in the range of: | Status    | Remarks   |
|--------------------------------------|-----------|---|
| < 30                                 | Poor      | There are inadequate noise mitigation measures on site. Try identifying and put up noise barriers for noisy machinery/ operations and work areas.                                     |
| 30 - 50                              | Average   | There should already be noise barriers and some sound-reduced machinery on site. You can improve by actively identifying noisy works/ machinery and enforcing good practices on site. |
| > 50                                 | Excellent | Well done! You have good noise mitigation and practices on site. Keep up your good work!  |



## Appendix 3

### Useful Information

## Community Engagement: Construction phase

| No. | Public Relations Work   | Scores |
|-----|---|--------|
| 1   | Community bonding/ information sharing sessions have been planned   | 2      |
| 2   | Circulars were sent out to affected residents in advance of night work and there are periodic publication to keep residents updated | 2      |
| 3   | The relevant authority has been informed in advance of any night work   | 2      |
| 4   | Hotlines and communication channels are made available for residents feedback   | 2      |
| 5   | There is an investigation team looking into feedback and getting back to the resident   | 2      |



## Appendix 3

### Useful Information

#### Score Results

Total possible marks for this section = 10 marks

| If your score falls in the range of: | Status    | Remarks  |
|--------------------------------------|-----------|--|
| < 5                                  | Poor      | Public relation works will help strengthen the existing measures you have on site. Do practice good public relation works in managing public expectations. |
| 5 - 7                                | Average   | You have sufficient public relation works in place. However there is still room for improvement.   |
| > 7                                  | Excellent | Keep up the good work! Continuous engagement of the public and relevant authorities will help you to keep your mitigation measures in check.               |



## References

### Legal and other requirements

1. Environmental Protection and Management Act
2. Environmental Protection and Management (Control of Noise at Construction Sites) Regulations.
3. CP 49: 1998 Code of Practice for Noise Control on construction and demolition sites

### LTA Contractual Specification

1. Annex A-g: Environmental Considerations of the General Specifications (February 2013 Edition)

### Websites

1. <http://www.nonoise.org>
2. <http://www.catseyeservices.com/Handbooks/cd/references/references.htm>
3. [http://www.epd.gov.hk/epd/english/environmentinhk/noise/noise\\_maincontent.html](http://www.epd.gov.hk/epd/english/environmentinhk/noise/noise_maincontent.html)
4. <http://citysoundproofing.com/>
5. <http://www.noisenet.org>
6. <http://www.techniconacoustics.com/acoustics-101/glossary>

